



January 31, 2005

SDMS Document ID

Ron McManamy Environmental Quality Management 6825 216th Street SW, Suite J Lynnwood, WA 98036

Re:

Decking upgrade Former Mobile Shop Stimpson Lumber Mill Libby, Montana

Ron,


As indicated in our "Pre-removal roof occupancy assessment" letter, dated 01/24/05, we have coordinated a cost effective eption to upgrade the existing roof decking in order to support construction loads. The upgrade shall be per the attached "Roof Framing Plan", sheet 1 of 2. New, (N), 6 ¾" x 10 ½" glu-lam roof rafters shall be placed in between each existing, (E), 8x12 roof rafters. These beams shall be installed prior to placing workers on the roof. Reference attached detail A, sheet 2 of 2, for (N) rafter to (E) truss connection. These (N) rafters on the attached "Roof Framing Plan", sheet 1 of 2, are shown, for clarity, to be in one location only but shall be used throughout the entire roof area.

We have analyzed the roof structure only for the loads incurred during removal of the concrete roof slab of the above noted structure. Our roof assessment was not performed to bring the existing building up to the requirements of the International Building Code, 2003 Edition. We hold no responsibility for any other element or the integrity of the structure as a whole. Please call with any specific questions.


Sincerely,

Eclipse Engineering, Inc.

Brian Hanson, P.E. Project Engineer




235 North 1st West, 2nd Floor Missoula, Montana 59802 Phone: (406) 721-5733 Fax: (406) 721-4988 www.eclipse-engineering.com



Eclipse Engineering, Inc.

235 N. First St. West Missoula, MT 59802 Second Floor Ph; (406) 721-5733 www.eclipse-engineering.com STIMPSON LUMBER MILL ROOF DECKING UPGRADE

DATE: 01/31/05 DRAWN BY: JAL DESIGN BY: BH



3/4" = 1'-0"

SCALE: